
Station Information Report

Solar and Meteorological Station

World Bank – Wadelai, Uganda



Revision	Date	Author	Checked	Approved	Comments
Rev 0	06 April 2020	H. Bester	J. van Jaarsveldt	M. de Jager	First Issue
Rev 1					
Rev 2					

Contents

1	Introduction	4
2	Station Summary	6
3	Map of area.....	7
4	Site layout.....	8
5	Instrument list, serial numbers and multipliers.....	10
6	Supporting hardware and communication peripherals.....	11
7	Data logger wiring	12
8	Power circuit diagram.....	14
9	Detail Photographs	15
10	Terrain Photographs.....	22
11	Station Photographs.....	28
12	Calibration Certificates	34

1 Introduction

NOTE: This project occurred during the COVID19 pandemic outbreak. Any impact on the data quality as a result of the pandemic will be recorded in the monthly quality feedback report alongside other noteworthy events for the affected month.

The World Bank initiated a project with funding from the Energy Sector Management Assistance Program (ESMAP) to, amongst others, support the East African Power Pool (EAPP) in doing renewable energy resource assessments. The focus for this particular section of the project is to get high quality bankable irradiance measurements, high quality supporting meteorological measurements and to promote the awareness of the resource potential of solar energy.

The project is orientated around sites considered for large-scale solar power plant development in the near future. The on-site measured data generated from this project for the applicable term is to be used in conjunction with overlapping and historic satellite derived data for the same location in order to generate a bankable data set, subsequently providing enhanced data accuracy for locations where there may be substantial project investments. The data complements the global resource data available for free via the Global Solar Atlas (<https://globalsolaratlas.info>).

GeoSUN Africa has been awarded the contract to execute the on-site measurement related aspects of the project. The assignment for GeoSUN Africa is the following:

- An inception mission which involves visiting the proposed site locations and selecting the optimal location for the measurement equipment. The outcome of this inception mission is this implementation plan where sites and stations tiers are proposed;
- Providing high quality measuring equipment for each site, in line with the technical specifications;
- Installation of measurement equipment as well as subsequent Site Installation Report and photographs for each site;
- Hosting and providing two years of high quality, 'bankable' meteorological data relevant for solar resource assessment and project development, including upload to an 'open data' platform for public dissemination;
- Ensuring maintenance, security, local cleaning/caretaking, and mitigation against extreme weather events and corrosion;
- Ensuring strong local involvement and capacity building at all stages of the measurement campaign;
- Decommissioning of all sites at the end of the measurement campaign, unless separate arrangements are made with one or more host institutions to continue with measurements outside of this assignment/contract.


This document acts as the Site Installation Report which follows the commissioning of the site, outlining the site location, site characteristics, technical specifications, calibration procedures, and all other relevant information to allow data users to fully understand the site and ensure the bankability of the measurement data. The Site Installation Report is contains photographs of the site and the surrounding terrain.

The measurement data from the site will be continuously transferred to GeoSUN's central data repository, and shall then be transferred to the World Bank on a monthly basis in both raw and

quality controlled formats according to the specifications developed by ESMAP. This data will be delivered via an online file sharing platform one month in arrears. Site Measurement Reports will accompany the delivery of monthly data, and shall detail any issues with the site or equipment, field calibration procedure, and any notable conclusions or results. The World Bank and key client counterparts shall also be provided with access to the vendor's data repository or monitoring platform for real-time analysis.

The assignment shall be deemed completed once two years of concurrent data is delivered in compliance with the minimum data recovery rates specified. At this point the vendor shall decommission each site and remove the solar measurement equipment, unless alternative arrangements outside the scope of this assignment/contract are made and endorsed by the relevant client/host agency.

2 Station Summary

Work performed	Installation and commissioning of solar and meteorological measurement station including security fence.
Commissioning date	17 January 2020
Planned decommissioning date	17 January 2022
Client	World Bank
Client contact person and contact details	<p>Name: Abdul Rahim Jalloh Email: Abduljay@gmail.com Telephone: + 1 301 825 1628</p> <p>Name: Chiara Rogate Email: crogate@worldbank.org Telephone: +1 202 250 0568</p> <p>Name: Job Kahororo Email: job.kahororo@uetcl.com Telephone: +256 772 360 185</p>
Site location	<p>375 km north west of Kampala, Uganda. 35 km north of the town Pakwach, Uganda.</p> 
Access	Starting in Pakwach, drive north to Gulu-Arua road. Turn right on Gulu-Arua road and head east. After 90 m turn left onto unmarked dirt road heading north west towards Pacego. After 34.6 km turn left and head west for 170 m. The station will be located on the left in a clearing.
Coordinates	02° 43' 33.4" N, 31° 23' 25.4" E (2.725961, 31.390403)
Elevation	644 m AMSL
Time zone (local and data logger)	GMT +3 local time zone
Name and contact details of on-site contact person(s)	Name: Samuel Ongiertho Cell: +256 705 522790

3 Map of area



Figure 1: Map of the surrounding area (Source: Google Earth)




Figure 2: Terrain horizon and day length (Source: Solargis)

4 Site layout




Figure 3: Site Layout (plan view)



Figure 4: Site Layout (perspective view)

5 Instrument list, serial numbers and multipliers

Instrument (Measurement)	Make and Model	Serial Number	Variable Name (Program)	Multiplier
Pyranometer (GHI)	Kipp & Zonen CMP 10	140513	GHI_1	9.37 $\mu\text{V/W/m}^2$
Pyranometer (GHI)	Kipp & Zonen CMP 10	151711	GHI_2	8.05 $\mu\text{V/W/m}^2$
Pyranometer (DHI)	Delta -T SPN 1	A2063	DHI_SPN1	1
Reference Cell Clean	Ingenieurbüro Si-mV-85-A	85-00205-17-19350070	RefCellClean	58.01 $\mu\text{V/W/m}^2$
Reference Cell Monthly	Ingenieurbüro Si-mV-85-A	85-00205-17-19350071	RefCellMonthly	57.72 $\mu\text{V/W/m}^2$
Reference Cell Dirty	Ingenieurbüro Si-mV-85-A	85-00205-17-19350072	RefCellDirty	58.10 $\mu\text{V/W/m}^2$
3-Cup Anemometer (Wind speed)	Young 03002 Wind Sentry	06750	WSpd	0.75 Offset 0.2 Slope
Wind Vane (Wind Direction)	Young 03002 Wind Sentry	06750	WDir	0 Offset 352 Slope
Temperature Sensor (Ambient Temperature)	Campbell Scientific CS215	E14827	Temp	1
Relative humidity Sensor (Relative Humidity)	Campbell Scientific CS215	E14827	RH	1
Barometer (Atmospheric Pressure)	Vaisala PTB110	N0640848	BP	500 offset 0.24 slope
Rain Gauge (Rain)	Texas Electronics TR-525I	47079-311	Rain	0.2 mm/tip
Corrosion Plate	Make	Sample	Position (Column, Row)	Mass (g)
Mild Steel plate (Corrosion Testing)	Orytech Mild Steel	I1	C6, R1	132.7200
		I2	C6, R2	134.8636
		I3	C2, R1	129.8555
		I4	C2, R2	133.9452
Galvanised (Zinc) plate (Corrosion Testing)	Orytech H.D. Galvanised (Zinc)	I1	C4, R1	80.8324
		I2	C4, R2	80.7524
		I3	C8, R1	79.8238
		I4	C8, R2	80.1664
Copper plate (Corrosion Testing)	Orytech Copper	I1	C3, R1	81.5997
		I2	C3, R2	82.3643
		I3	C7, R1	82.4438
		I4	C7, R2	81.3196
Aluminium plate (Corrosion Testing)	Orytech Aluminium	I1	C5, R1	37.7258
		I2	C5, R2	37.9714
		I3	C1, R1	37.3333
		I4	C1, R2	37.2100

6 Supporting hardware and communication peripherals

Data Logger	Campbell CR1000 (OS:Std.32.03)
Communication	RS232 (115200) TCP/IP
Pakbus Address	778
Password Set	None
Modem and Antenna	Maestro M100 3G modem with Poynting antenna
Network Details	Service provider: Airtel Phone number: +256 759 732 713
Modem Power Control	SW12V
Data Logger Clock	GMT+3
Main Battery	2 x 12 V / 24 Ah
Solar Panel(s)	2 x 25 W
Charge Controller	2 x CPL Research (10 A)

7 Data logger wiring

E.Africa Wiring Diagram November 2019							
Logger Port	Accessories	Connection	Instrument Cable	Function	Reading	Instrument	
C8		1H	White	Signal +	GHI1	SR20	
		1L	Green	Signal -			
		AGB	Black	Shield			
	Relay 1 NO		Yellow	Heater +			
	VX3	10kΩ 0.1% Resistor	GB	Brown			Heater -
			SE3	Pink			Temp +
			AG1	Grey			Temp -
				Blue			Temp -
			3H	White / Red			Signal +
				3L			Green / Blue
C8		AGB	Black	GND	GHI2	SR20 / CMP	
		Relay 1 NO		Yellow			Heater +
		GB		Heater -			
	VX1	10kΩ 0.1% Resistor	SE4	Red			Temp +
			AG2	Blue			Temp -
				5H			White
			6H	Brown			DHI +
				5L			Green
			6L				
				GB			Grey
		PB	Pink	12 V			
			Relay 1 NO		Red	Heater +	
		GB	Blue	Heater -			
			AGB	Clear	GND		
		NC	Yellow	Sun			
			PB	Red	12 V		
		C1	Green	Signal +	Temp & RH	CS215	
			GB	White			0 V
		GB	Black	0 V			
			AGB	Clear	GND		
		SE13	Red	Signal +	Clean	Ref cell	
			AG6	Blue			Signal -
		AGB	Black	GND			
			SE14	Red	Signal +		
		AG7	Blue	Signal -	Monthly	Ref cell	
			AGB	Black			GND
		SE15	Red	Signal +	Dirty	Ref cell	
			AG7	Blue			Signal -
		AGB	Black	GND			
			VX2	Black	Excitation		
		SE16	Red	Signal +	WD	024A	
			AG8	White			Signal -
		AGB	Clear	GND			
			P1	Black	Signal +		
		AG	White	Signal -	WS	014A	
			AGB	Clear			GND

Solar & Meteorological Station – Installation Report



		P2	Black	Signal +	Rain	TE525
		AG	White	Signal -		
		AGB	Clear	GND		
5V	10kΩ Resistor	C2	Red	Signal +	Clean	Clean Button
		C5	Green	Light +		
		C3	Blue	Signal -		
		AGB	Clear	GND		
5V	10kΩ Resistor	C4	Yellow	Signal +	Monthly	Monthly Button
		C5	Green	Light +		
		C3	Blue	Signal -		
		AGB	Clear	GND		
5V	10kΩ Resistor	C6	Red	Signal +	Gate	Switch
		G	Blue	Signal -		
		AGB	Clear	GND		
		SE4	Blue/Brown	Signal +	Pressure	PTB110
		PB	Red	12V		
		C7	Green	Signal +		
		GB	Black	Signal -		
		AG	Yellow/White	GND		
		AGB	Clear	GND		

8 Power circuit diagram




Figure 5: The DC power circuit

9 Detail Photographs

This section showcases details of the installation, including the main station components. Records are shown of instrument makes, models and serial numbers, as well as the installation levels and orientation where applicable.



Figure 6: Station Summary



Figure 7: GHI (1) Pyranometer Installation



Figure 8: GHI (2) Pyranometer Installation



Figure 9: DHI Pyranometer Installation



Figure 10: Wind instruments at 3 m



Figure 11: Thermometer and Hygrometer at 2 m



Figure 12: Corrosion Test Stand



Figure 13: Rain Gauge




Figure 14: Barometer



Figure 15: Reference Cells at 10° South



Figure 16: Solar Panels



Figure 17: Logger Enclosure

10 Terrain Photographs

Obstacles protruding higher than the horizon as viewed from the solar instruments will affect lower solar elevation readings if they fall within the sun path as depicted in Figure 2. The pictures in this section shows the terrain surrounding the station at the time of installation, giving an indication of near or far shading influences on the station.



Figure 17: 0/360 Degrees (North)



Figure 18: 30 Degrees



Figure 19: 60 Degrees



Figure 20: 90 Degrees (East)



Figure 21: 120 Degrees



Figure 22: 150 Degrees



Figure 23: 180 Degrees (South)



Figure 24: 210 Degrees



Figure 25: 240 Degrees



Figure 26: 270 Degrees (West)



Figure 27: 300 Degrees



Figure 28: 330 Degrees

11 Station Photographs

This section indicates the station within the surrounding terrain to give an overall view thereof, as well as provide additional context to the possible near and far shading influences.



Figure 29: 0/360 Degrees (From North)



Figure 30: 30 Degrees



Figure 31: 60 Degrees



Figure 32: 90 Degrees (From East)



Figure 33: 120 Degrees



Figure 34: 150 Degrees



Figure 35: 180 Degrees (From South



Figure 36: 210 Degrees



Figure 37: 240 Degrees



Figure 38: 270 Degrees (From West)



Figure 39: 300 Degrees



Figure 40: 330 Degrees

12 Calibration Certificates

Calibration Certificate




Pyranometer ISO 9847 Calibration Certificate Number: GSACA-0804

Calibrated Instrument	
Instrument: Pyranometer	Calibration Date: 05 July 2019
Manufacturer: Kipp & Zonen	Serial Number: 140513
Model: CMP10	New Sensitivity: 9.37 $\mu\text{V}/\text{W}/\text{m}^2$
ISO 9060:1990 Class: Secondary Standard	

Calibration Methodology
 GeoSUN performed an outdoor calibration through exposure of both the calibrated instrument (instrument under test) and a reference instrument with the sun and sky radiation as the source and comparing the sensor outputs. The instruments were installed on a common solar tracker and regularly checked to ensure that it remained clean and aligned for the duration of the reference data being collected. The calibration was performed in accordance with the ISO 9847 (1992) standard, procedure type Ic.

Reference Instrument and its Traceability
 The reference instrument is a Kipp & Zonen CMP21 pyranometer (SN 110811). The instrument was calibrated on 14 August 2018 at ISO-CAL North America against absolute cavity radiometer AHF-28560 which successfully participated at IPC-XII with the World Standard Group of radiometers. The location of ISO-CAL is at 20th street, Phoenix, Arizona in the USA at latitude 33.8176944°, longitude -112.0396083° and altitude 570 m AMSL. The reference instrument was calibrated at normal incidence with the sun and sky radiation as the source using the "alternating sun-and-shade method". The readings are referenced to the World Radiometric Reference (WRR) as stated in the WMO Technical Regulations, originally with an SI relative uncertainty estimated at $\pm 0.3\%$. The diagram on the right shows the traceability hierarchy.



Absolute Uncertainty
 The absolute uncertainty is the combined result of three uncertainties namely:
 1) The expanded uncertainty during calibration of the reference instrument, given as $\pm 0.44\%$.
 2) The uncertainty in the correction of directional errors (cosine errors), estimated by scientific judgement as $\pm 0.5\%$.
 3) The expanded uncertainty of the transfer procedure (calibration by comparison), estimated by scientific judgement as $\pm 1\%$.
 The combined expanded uncertainty is the root sum of the squares, resulting in $\sqrt{(0.44^2 + 0.5^2 + 1^2)} = \pm 1.20\%$.

Calibration Environment, Results and Instrument Status
 The calibration was performed at latitude -33.928973°, longitude 18.865208° and altitude 122 m AMSL and was concluded on 05 July 2019 at 15:33. A calibration was done using the measured output of the test instrument, of which the calibration environment and results are stated below. The measurement results recorded in this certificate were correct at the time of calibration. The subsequent accuracy will depend on factors such as care, handling and frequency of use. The calibration certificate or report may not be reproduced except in full, without the written approval of the laboratory. Considering the operating conditions and the IEC 61724-1:2017 standard requirements, GeoSUN recommends an annual calibration.

<p>Instrument Status Bubble Level: Good Dome: Good</p>	<p>Calibration Environment - Average [Range] Irradiation: 997 [922 - 1023] W/m^2 Ambient Temperature: 16.6 [14.4 - 18.4] $^{\circ}\text{C}$ Reference Instrument Temp.: 20.4 [16.9 - 22.7] $^{\circ}\text{C}$ Solar Elevation: 30.4 [20.8 - 33.3] $^{\circ}$ Linke Turbidity Factor: 3.1 [2.8 - 4.0]</p>
<p>Original Calibration Original Sensitivity: 9.29 $\mu\text{V}/\text{W}/\text{m}^2$ Original Calib. Date: 23 April 2014</p>	<p>Calibration Results New Sensitivity: 9.36632 $\mu\text{V}/\text{W}/\text{m}^2$ Sensitivity Standard Deviation (σ_{n-1}): 0.00673 $\mu\text{V}/\text{W}/\text{m}^2$ Calibration Uncertainty ($k = 2$): $\pm 0.1125 \mu\text{V}/\text{W}/\text{m}^2$ ($\pm 1.20\%$) Data Quantity (Recorded Over 1 Day): 15 Series, 315 Samples Next Calibration: July 2020</p>

Calibrated by: W.C. Engelbrecht

Authorised by: M.L. de Jager



GeoSUN Africa (Pty) Ltd
 Unit 1, CS Africa Building, 1 Meson Street, Techno Park, Stellenbosch, South Africa
 info@geosun.co.za, www.geosun.co.za, +27 21 882 8354

V2019/07/16
 Page 1 of 1
 End of certificate

Calibration Certificate



Pyranometer ISO 9847 Calibration Certificate Number: GSACA-0819


<p>Calibrated Instrument</p> <p>Instrument: Pyranometer Manufacturer: Kipp & Zonen Model: CMP10 ISO 9060:1990 Class: Secondary Standard</p>	<p>Calibration Date: 06 August 2019 Serial Number: 151711 New Sensitivity: 8.05 $\mu\text{V}/\text{W}/\text{m}^2$</p>
---	--

Calibration Methodology

GeoSUN performed an indoor calibration through exposure of both the calibrated instrument (instrument under test) and a reference instrument to an artificial light as radiation source and comparing the sensor outputs. The instruments were installed on a common horizontal base and regularly checked to ensure that it remained clean and level for the duration of the reference data being collected. The calibration was performed in accordance with the ISO 9847 (1992) standard, procedure type IIC.

Reference Instrument and its Traceability

The reference instrument is a Kipp & Zonen CMP21 pyranometer (SN 110811). The instrument was calibrated on 14 August 2018 at ISO-CAL North America against absolute cavity radiometer AHF-28560 which successfully participated at IPC-XII with the World Standard Group of radiometers. The location of ISO-CAL is at 20th street, Phoenix, Arizona in the USA at latitude 33.8176944°, longitude -112.0396083° and altitude 570 m AMSL. The reference instrument was calibrated at normal incidence with the sun and sky radiation as the source using the "alternating sun-and-shade method". The readings are referenced to the World Radiometric Reference (WRR) as stated in the WMO Technical Regulations, originally with an SI relative uncertainty estimated at $\pm 0.3\%$. The diagram on the right shows the traceability hierarchy.



Absolute Uncertainty

The absolute uncertainty is the combined result of three uncertainties namely:

- 1) The expanded uncertainty during calibration of the reference instrument, given as $\pm 0.44\%$.
- 2) The uncertainty in the correction of directional errors (cosine errors), estimated by scientific judgement as $\pm 0.5\%$.
- 3) The expanded uncertainty of the transfer procedure (calibration by comparison), estimated by scientific judgement as $\pm 1\%$.

The combined expanded uncertainty is the root sum of the squares, resulting in $\sqrt{(0.44^2 + 0.5^2 + 1^2)} = \pm 1.20\%$.

Calibration Environment, Results and Instrument Status

The calibration was performed at latitude -33.965467°, longitude 18.836348° and altitude 134 m AMSL and was concluded on 06 August 2019 at 10:55. A calibration was done using the measured output of the test instrument, of which the calibration environment and results are stated below. The measurement results recorded in this certificate were correct at the time of calibration. The subsequent accuracy will depend on factors such as care, handling and frequency of use. The calibration certificate or report may not be reproduced except in full, without the written approval of the laboratory. Considering the operating conditions and the IEC 61724-1:2017 standard requirements, GeoSUN recommends an annual calibration.

Instrument Status

Bubble Level: Good
 Dome: Good

Calibration Environment - Average [Range]

Irradiation: 571 [528 - 614] W/m^2
 Ambient Temperature: 20.1 [19.4 - 20.5] $^{\circ}\text{C}$
 Reference Instrument Temp.: 20.6 [19.6 - 21.2] $^{\circ}\text{C}$

Original Calibration

Original Sensitivity: 8.04 $\mu\text{V}/\text{W}/\text{m}^2$
 Original Calib. Date: 28 August 2015

Calibration Results

New Sensitivity: 8.05152 $\mu\text{V}/\text{W}/\text{m}^2$
 Sensitivity Standard Deviation (σ_{n-1}): 0.00203 $\mu\text{V}/\text{W}/\text{m}^2$
 Calibration Uncertainty ($k = 2$): $\pm 0.0967 \mu\text{V}/\text{W}/\text{m}^2$ ($\pm 1.20\%$)
 Data Quantity : 4 Series, 16 Samples
 Next Calibration: August 2020

Calibrated by:
 W.C. Engelbrecht

Authorised by:
 M.L. de Jager




GeoSUN Africa (Pty) Ltd
 Unit 1, CS Africa Building, 1 Meson Street, Techno Park, Stellenbosch, South Africa
 info@geosun.co.za, www.geosun.co.za, +27 21 882 8354

V2019/07/16
 Page 1 of 1
 End of certificate

AT	<i>Delta-T Devices Ltd</i>
SPN1 Sunshine Pyranometer	

Calibration Certificate

This is to certify that the Sunshine Pyranometer type SPN1 identified below has been calibrated in accordance with Delta-T Devices Ltd standard production procedures and conforms to the specifications as detailed.

Serial Number	SPN1 – A2063
Date	24/09/19
Authorised Signature	

We recommend that this instrument is recalibrated every 2 years.

Traceability

The SPN1 is calibrated under a uniform light source which simulates the solar spectrum, against a transfer standard SPN1. The transfer standard is calibrated outdoors against a Kipp & Zonen CM21 secondary standard pyranometer (calibration traceable to the World Radiometric Reference), with solar tracker and shading disk for diffuse measurement.

Accuracy, Total (Global) and Diffuse radiation

When correctly calibrated, the expected accuracy is given in the table below. The figures give 95% confidence limits, i.e. 95% of individual readings will be within the stated limits under normal climatic conditions.

Overall accuracy:	±5% daily integrals ±5% ±10 W.m ⁻² hourly averages ±8% ±10 W.m ⁻² individual readings
Range	0 to >2000 W.m ⁻²
Analogue output sensitivity	1mV = 1 W.m ⁻²



Delta-T Devices Ltd
 130 Low Road, Burwell, Cambridge, CB25 0EJ, UK
 Tel: +44 1638 742922 Fax: +44 1638 743155
 email: sales@delta-t.co.uk web: www.delta-t.co.uk


Calibration Certificate Silicon Irradiance Sensor

Sensor Type: **SI-mV-85-A**
 Serial No.: **85-00205-17-19350070**
 Comment:

Irradiance Calibration with Artificial Light in Comparison to a Reference Cell

Calibrated by: **Huhnstock-Breuer**
 Date / Time: **28.08.2019 13:42**

	Type	Calibration $\mu\text{V}/\text{W}/\text{m}^2$	Temperature Coefficient $1/^\circ\text{C}$	Output mV	Temperature $^\circ\text{C}$	Irradiance ¹⁾ W/m^2
Reference Cell	Si-Ref mono PTB-1	56,51	0,00067	56,953	30,76	1004,0
	Type	Irradiance W/m^2	Correction Factor ³⁾	Output mV	Temperature $^\circ\text{C}$	Calibration $\mu\text{V}/\text{W}/\text{m}^2$
Test Object	SI-mV-85-A	1004,0	0,995498	58,506	31,46	58,01



INGENIEURBÜRO
 Mencke & Tegtmeier GmbH
 Meßgeräte für die Solartechnik
 Schwarzer Weg 43A
 31789 Hameln, Germany
 www.ib-mut.de

Test Equipment Irradiance Calibration

Manufacturer	Type	Serial No.	Calibration Certificate	Trace
Ingenieurbüro Mencke & Tegtmeier GmbH	Si-Ref mono PTB-1	02-20002-05-15309999	47109-PTB-18	PTB
Gantner Instruments	IDL100	191667	098220-02 D-K-15019-01-00	DKD
	ISM111	078743	098221-02 D-K-15019-01-00	DKD
OMEGA Engineering	IN510	9894	.i.	.i.

¹⁾
$$\text{Irradiance} = \frac{\text{Output} \cdot 1000}{\text{Calibration} \cdot (1 + \text{Temperature Coefficient} \cdot (\text{Temperature} - 25))}$$

²⁾
$$\text{Calibration} = \frac{\text{Output} \cdot 1000 \cdot \text{Correction Factor}}{\text{Irradiance}}$$

³⁾ Individual calculated for each Calibration Process, must not be used for Outdoor Application.



INGENIEURBÜRO
 Mencke & Tegtmeier GmbH
 Meßgeräte für die Solartechnik
 Schwarzer Weg 43A
 31789 Hameln, Germany
 www.ib-mut.de

Calibration Certificate Silicon Irradiance Sensor

Sensor Type: **Si-mV-85-A**
 Serial No.: **85-00205-17-19350071**
 Comment:

Irradiance Calibration with Artificial Light in Comparison to a Reference Cell

Calibrated by: **Huhnstock-Breuer**
 Date / Time: **28.08.2019 13:42**

	Type	Calibration μV/W/m ²	Temperature Coefficient 1/°C	Output mV	Temperature °C	Irradiance ¹⁾ W/m ²
Reference Cell	Si-Ref mono PTB-1	56,51	0,00067	56,953	30,76	1004,0
	Type	Irradiance W/m ²	Correction Factor ³⁾	Output mV	Temperature °C	Calibration μV/W/m ²
Test Object	Si-mV-85-A	1004,0	0,995880	58,192	30,91	57,72

Test Equipment Irradiance Calibration

Manufacturer	Type	Serial No.	Calibration Certificate	Trace
Ingenieurbüro Mencke & Tegtmeier GmbH	Si-Ref mono PTB-1	02-20002-05-15309999	47109-PTB-18	PTB
Gantner Instruments	IDL100	191667	098220-02 D-K-15019-01-00	DKD
OMEGA Engineering	ISM111	078743	098221-02 D-K-15019-01-00	DKD
	IN510	9894	.i.	.i.

$$^1) Irradiance = \frac{Output * 1000}{Calibration * (1 + Temperature Coefficient * (Temperature - 25))}$$

$$^2) Calibration = \frac{Output * 1000 * Correction Factor}{Irradiance}$$

³⁾ Individual calculated for each Calibration Process, must not be used for Outdoor Application.


Calibration Certificate Silicon Irradiance Sensor

Sensor Type: Si-mV-85-A
Serial No.: 85-00205-17-19350072
Comment:

Irradiance Calibration with Artificial Light in Comparison to a Reference Cell

Calibrated by: Huhnstock-Breuer
Date / Time: 28.08.2019 13:42

	Type	Calibration μV/W/m ²	Temperature Coefficient 1/°C	Output mV	Temperature °C	Irradiance ¹⁾ W/m ²
Reference Cell	Si-Ref mono PTB-1	56,51	0,00067	56,953	30,76	1004,0
	Type	Irradiance W/m ²	Correction Factor ³⁾	Output mV	Temperature °C	Calibration μV/W/m ²
Test Object	Si-mV-85-A	1004,0	0,995783	58,576	31,05	58,10



INGENIEURBÜRO
 Mencke & Tegtmeyer GmbH
 Meßgeräte für die Solartechnik
 Schwarzer Weg 43A
 31789 Hameln, Germany
 www.lg-mut.de

Test Equipment Irradiance Calibration

Manufacturer	Type	Serial No.	Calibration Certificate	Trace
Ingenieurbüro Mencke & Tegtmeyer GmbH	Si-Ref mono PTB-1	02-20002-05-15309999	47109-PTB-18	PTB
Gantner Instruments	IDL100	191667	098220-02 D-K-15019-01-00	DKD
	ISM111	078743	098221-02 D-K-15019-01-00	DKD
OMEGA Engineering	IN510	9894	J.	J.

¹⁾
$$Irradiance = \frac{Output * 1000}{Calibration * (1 + Temperature Coefficient * (Temperature - 25))}$$

²⁾
$$Calibration = \frac{Output * 1000 * Correction Factor}{Irradiance}$$

³⁾ Individual calculated for each Calibration Process, must not be used for Outdoor Application.

Calibration Certificate



ISO 9001 Meteorological Calibration

Calibration Number: GSACM-0062

Station Name: Wadelai Meteorological Station
Location: -33.965447°, 18.8361658°

Calibration Date: 25 November 2019
 Ambient conditions: 28 - 29 °C; 49 - 50 % RH

Test Instrument	Parameter	Reference Reading	Test Reading	Uncertainty (±)*	
				Instr.	Absolute
Campbell Scientific Model CS215 SN E14527	Ambient Temperature	1.5 °C 42.4 °C	1.4 °C 42.1 °C	0.9 °C	1.9 °C
Campbell Scientific Model CS215 SN E14527	Relative Humidity At 29°C → At 29°C →	18.0 % RH 70.0 % RH	18.6 %RH 69.8 % RH	2 % RH	5.6 % RH
Vaisala PTB110 SN N0640848	Barometric Pressure	700.0 hPa 800.7 hPa 900.1 hPa 1006.7 hPa	700.9 hPa 800.1 hPa 900.7 hPa 1006.0 hPa	1.5 hPa	2.7 hPa
RM Young 03002-5 SN 06750	Wind Speed $m/s = (rpm \times 0.0125) + 0.2$	200 rpm → 400 rpm → 800 rpm → 1 800 rpm → 2 400 rpm → 3 000 rpm →	2.7 m/s 5.2 m/s 10.2 m/s 22.7 m/s 30.2 m/s 37.7 m/s	0.5 m/s	0.5 m/s
RM Young 03002-5 SN 06750	Wind direction	North East South West	0 ° 90 ° 180 ° 270 °	5 °	10 °
Texas TR525I SN 47079-311	Precipitation $Tips = \frac{ml}{4.73 ml/Tip}$	250 ml 52 Tips	51 Tips	7.5 ml 1 Tip	11.5 ml 2 Tips

Comments: The rain gauge sensitivity was adjusted.

Reference Instruments

Parameter	Reference Instrument	Serial Number	Traceability	Calibration Date	Uncertainty (±)	
					Instr.	Expanded*
Temperature	Campbell Scientific 109	15553-29	South African National Standard (NMISA)	05-Sep-19	0.01	1.02 °C
Relative Humidity	Rotronic HC2A-SH	20261232	Swiss National Standard (Rotronic)	03-Sep-19	1.1	3.6 % RH
Barometric Pressure	Vaisala PTB110	L2850725	South African National Standard (Inteltronics)	09-Sep-19	0.2	1.2 hPa
Precipitation	Glassco Measuring Cyl.	05.15/2028	Indian National Standard (Glassco)	19-Sep-19	3	4.02 ml
Wind Speed	Young 18802 Drive	4664	South African National Standard (LabCom)	28-Aug-19	2	3 rpm

* Expanded uncertainty includes the reference's accuracy and calibration uncertainty, and this calibration's transfer uncertainty. Absolute calibration uncertainty includes the test instrument accuracy. Although the test instrument increment resolution can have an effect on the uncertainty, it is not taken into account.

Calibration Methodology

- Temperature: Reference and test instruments were sealed and submerged in warm and cold water sources for respective measurements.
- Relative Humidity: Reference and test instruments were tested in a low humidity chamber and at ambient conditions.
- Barometric Pressure: Reference and test instruments were connected to a closed pressure system and different pressures were induced.
- Precipitation: A set volume of water was poured through the rain gauge at an acceptable flow rate and the amount of tips were counted.
- Wind Speed: A drive was coupled to the anemometer shaft, set rotational speeds were applied and wind speed recorded.
- Wind Direction: The wind vane was handheld at roughly 90° increment angles while angle outputs were recorded.

Calibrated by: W.C. Engelbrecht

Approved by: M.L. de Jager



GeoSUN Africa (Pty) Ltd
 Unit 1, CS Africa Building, 1 Meson Street, Techno Park, Stellenbosch, South Africa
 info@geosun.co.za, www.geosun.co.za, +27 21 882 8354

2018/06/16