

**Deutsche WindGuard
Wind Tunnel Services GmbH, Varel**

**DEUTSCHE
WINDGUARD**

accredited by the / akkreditiert durch die

Deutsche Akkreditierungsstelle GmbH

as calibration laboratory in the / als Kalibrierlaboratorium im

Deutschen Kalibrierdienst

DKD



Deutsche
Akkreditierungsstelle
D-K-15140-01-00

| |
|-------------|
| 1620404 |
| D-K- |
| 15140-01-00 |
| 02/2016 |

Calibration certificate
Kalibrierschein

Calibration mark
Kalibrierzeichen

Object
Gegenstand

Wind Vane

Manufacturer
Hersteller

Thies Clima
D-37083 Göttingen

Type
Typ

4.3151.00.901

Serial number
Fabrikat/Serien-Nr.

09150128

Customer
Auftraggeber

Ammonit Measurement GmbH
D-10997 Berlin

Order No.
Auftragsnummer

L23835

Project No.
Projektnummer

VT160176

Number of pages
Anzahl der Seiten

6

Date of Calibration
Datum der Kalibrierung

02.02.2016

This calibration certificate documents the traceability to national standards, which realize the units of measurement according to the International System of Units (SI).

The DAkkS is signatory to the multilateral agreements of the European co-operation for Accreditation (EA) and of the International Laboratory Accreditation Cooperation (ILAC) for the mutual recognition of calibration certificates. The user is obliged to have the object recalibrated at appropriate intervals.

Dieser Kalibrierschein dokumentiert die Rückführung auf nationale Normale zur Darstellung der Einheiten in Übereinstimmung mit dem Internationalen Einheitensystem (SI).

Die DAkkS ist Unterzeichner der multilateralen Übereinkommen der European co-operation for Accreditation (EA) und der International Laboratory Accreditation Cooperation (ILAC) zur gegenseitigen Anerkennung der Kalibrierscheine. Für die Einhaltung einer angemessenen Frist zur Wiederholung der Kalibrierung ist der Benutzer verantwortlich.

This calibration certificate may not be reproduced other than in full except with the permission of both the German Accreditation Body and the issuing laboratory. Calibration certificates without signature are not valid. This calibration certificate has been generated electronically.

Dieser Kalibrierschein darf nur vollständig und unverändert weiterverbreitet werden. Auszüge oder Änderungen bedürfen der Genehmigung sowohl der Deutschen Akkreditierungsstelle als auch des ausstellenden Kalibrierlaboratoriums. Kalibrierscheine ohne Unterschrift haben keine Gültigkeit. Dieser Kalibrierschein wurde elektronisch erzeugt.

Date
Datum

Head of the calibration laboratory
Leiter des Kalibrierlaboratoriums

02.02.2016

Dipl. Phys. Dieter Westermann

Person in charge
Bearbeiter

Dipl.-Ing. (FH) Catharina Herold

| |
|-------------|
| 1620404 |
| D-K- |
| 15140-01-00 |
| 02/2016 |

| | | | | | | | | | | | |
|---|---|------------------|-----------------------|-------------------------|----------------------|---------------------------|----------------|------------------------------|-----------|------------------|------|
| Calibration object <i>Kalibiergegenstand</i> | Wind Vane | | | | | | | | | | |
| Calibration procedure <i>Kalibrierverfahren</i> | <ul style="list-style-type: none"> • Deutsche WindGuard Wind Tunnel Services: QM-KL-WRK-VA <p>Based on following standards:</p> <ul style="list-style-type: none"> • IEC 61400-12-1: Power performance measurements of electricity producing wind turbines • IEC 61400-12-2: Power performance of electricity producing wind turbines based on nacelle anemometry • ISO 16622: Meteorology - Sonic anemometers/thermometers • ASTM 5366-96: Standard Test Method of Measuring the Dynamic Performance of Wind Vanes | | | | | | | | | | |
| Place of calibration <i>Ort der Kalibrierung</i> | Windtunnel of Deutsche WindGuard WindTunnel Services GmbH, Varel | | | | | | | | | | |
| Test conditions <i>Messbedingungen</i> | <table border="0"> <tr> <td>wind tunnel area</td> <td>10000 cm²</td> </tr> <tr> <td>anemometer frontal area</td> <td>200 cm²</td> </tr> <tr> <td>diameter of mounting pipe</td> <td>34 mm</td> </tr> <tr> <td>blockage ratio ¹⁾</td> <td>0.020 [-]</td> </tr> <tr> <td>software version</td> <td>7.64</td> </tr> </table> | wind tunnel area | 10000 cm ² | anemometer frontal area | 200 cm ² | diameter of mounting pipe | 34 mm | blockage ratio ¹⁾ | 0.020 [-] | software version | 7.64 |
| wind tunnel area | 10000 cm ² | | | | | | | | | | |
| anemometer frontal area | 200 cm ² | | | | | | | | | | |
| diameter of mounting pipe | 34 mm | | | | | | | | | | |
| blockage ratio ¹⁾ | 0.020 [-] | | | | | | | | | | |
| software version | 7.64 | | | | | | | | | | |
| | ¹⁾ Due to the special construction of the test section no blockage correction is necessary. | | | | | | | | | | |
| Ambient conditions <i>Umgebungsbedingungen</i> | <table border="0"> <tr> <td>air temperature</td> <td>20.5 °C ± 0.1 °C</td> </tr> <tr> <td>air pressure</td> <td>1004.6 hPa ± 0.3 hPa</td> </tr> <tr> <td>relative air humidity</td> <td>49.1 % ± 2.0 %</td> </tr> </table> | air temperature | 20.5 °C ± 0.1 °C | air pressure | 1004.6 hPa ± 0.3 hPa | relative air humidity | 49.1 % ± 2.0 % | | | | |
| air temperature | 20.5 °C ± 0.1 °C | | | | | | | | | | |
| air pressure | 1004.6 hPa ± 0.3 hPa | | | | | | | | | | |
| relative air humidity | 49.1 % ± 2.0 % | | | | | | | | | | |
| Measurement uncertainty <i>Messunsicherheit</i> | <p>The expanded uncertainty assigned to the measurement results is obtained by multiplying the standard uncertainty by the coverage factor $k = 2$. It has been determined in accordance with DAkkS-DKD-3. The value of the measurand lies within the assigned range of values with a probability of 95%.</p> <p>The reference flow speed measurement is traceable to the German NMI (Physikalisch-Technische Bundesanstalt) standard for flow speed. It is realized by using a PTB owned and calibrated Laser Doppler Anemometer (Standard Uncertainty 0.2 %, $k=2$)</p> | | | | | | | | | | |
| Additional remarks <i>Zusätzliche Anmerkungen</i> | - | | | | | | | | | | |

| |
|-------------|
| 1620404 |
| D-K- |
| 15140-01-00 |
| 02/2016 |

Calibration result (1/3)
Kalibrierergebnis (1/3)

| Bin | Flow dir | Sensor out | Uncertainty | Flow speed |
|-----|----------|------------|-------------|------------|
| - | deg | deg | deg | m/s |
| 1 | 5.02 | 5.69 | 0.8 | 8.198 |
| 2 | 10.00 | 10.60 | 0.8 | 8.197 |
| 3 | 15.01 | 15.79 | 0.8 | 8.196 |
| 4 | 20.00 | 20.62 | 0.8 | 8.199 |
| 5 | 25.00 | 25.65 | 0.8 | 8.194 |
| 6 | 29.99 | 30.74 | 0.8 | 8.199 |
| 7 | 34.84 | 35.62 | 0.8 | 8.199 |
| 8 | 39.97 | 40.50 | 0.8 | 8.197 |
| 9 | 44.95 | 45.64 | 0.8 | 8.195 |
| 10 | 49.97 | 50.81 | 0.8 | 8.196 |
| 11 | 54.59 | 55.45 | 0.8 | 8.200 |
| 12 | 59.97 | 60.80 | 0.8 | 8.196 |
| 13 | 64.96 | 65.76 | 0.8 | 8.195 |
| 14 | 69.96 | 70.78 | 0.8 | 8.194 |
| 15 | 74.98 | 75.82 | 0.8 | 8.195 |
| 16 | 79.94 | 80.75 | 0.8 | 8.194 |
| 17 | 84.96 | 85.67 | 0.8 | 8.196 |
| 18 | 89.99 | 90.66 | 0.8 | 8.196 |
| 19 | 94.96 | 95.67 | 0.8 | 8.201 |
| 20 | 99.95 | 100.48 | 0.8 | 8.197 |
| 21 | 104.98 | 105.49 | 0.8 | 8.200 |
| 22 | 110.00 | 110.65 | 0.8 | 8.194 |
| 23 | 114.98 | 115.73 | 0.8 | 8.195 |
| 24 | 119.95 | 120.72 | 0.8 | 8.196 |
| 25 | 125.03 | 125.92 | 0.8 | 8.197 |
| 26 | 130.01 | 130.97 | 0.8 | 8.195 |
| 27 | 134.98 | 135.78 | 0.8 | 8.197 |
| 28 | 139.99 | 140.73 | 0.8 | 8.196 |
| 29 | 145.03 | 145.88 | 0.8 | 8.201 |
| 30 | 150.05 | 150.65 | 0.8 | 8.193 |

1620404

D-K-

15140-01-00

02/2016

Calibration result (2/3)*Kalibrierergebnis (2/3)*

| Bin | Flow dir | Sensor out | Uncertainty | Flow speed |
|-----|----------|------------|-------------|------------|
| - | deg | deg | deg | m/s |
| 31 | 155.06 | 155.73 | 0.8 | 8.198 |
| 32 | 160.02 | 160.71 | 0.8 | 8.193 |
| 33 | 165.01 | 165.76 | 0.8 | 8.195 |
| 34 | 169.95 | 170.65 | 0.8 | 8.194 |
| 35 | 174.97 | 175.68 | 0.8 | 8.200 |
| 36 | 179.96 | 180.59 | 0.8 | 8.196 |
| 37 | 184.95 | 185.54 | 0.8 | 8.197 |
| 38 | 189.97 | 190.45 | 0.8 | 8.198 |
| 39 | 195.03 | 195.53 | 0.8 | 8.193 |
| 40 | 199.98 | 200.48 | 0.8 | 8.198 |
| 41 | 205.05 | 205.57 | 0.8 | 8.199 |
| 42 | 210.08 | 210.62 | 0.8 | 8.201 |
| 43 | 215.10 | 215.60 | 0.8 | 8.198 |
| 44 | 220.01 | 220.57 | 0.8 | 8.199 |
| 45 | 224.96 | 225.51 | 0.8 | 8.201 |
| 46 | 229.95 | 230.43 | 0.8 | 8.201 |
| 47 | 235.01 | 235.53 | 0.8 | 8.199 |
| 48 | 239.99 | 240.49 | 0.8 | 8.201 |
| 49 | 245.03 | 245.47 | 0.8 | 8.198 |
| 50 | 249.98 | 250.44 | 0.8 | 8.202 |
| 51 | 254.95 | 255.43 | 0.8 | 8.197 |
| 52 | 259.96 | 260.53 | 0.8 | 8.195 |
| 53 | 265.00 | 265.49 | 0.8 | 8.199 |
| 54 | 270.01 | 270.48 | 0.8 | 8.198 |
| 55 | 274.99 | 275.52 | 0.8 | 8.197 |
| 56 | 279.97 | 280.35 | 0.8 | 8.201 |
| 57 | 285.01 | 285.41 | 0.8 | 8.201 |
| 58 | 290.02 | 290.51 | 0.8 | 8.196 |
| 59 | 295.00 | 295.41 | 0.8 | 8.195 |
| 60 | 299.97 | 300.39 | 0.8 | 8.201 |
| 61 | 304.99 | 305.47 | 0.8 | 8.196 |
| 62 | 309.98 | 310.44 | 0.8 | 8.200 |

| |
|-------------|
| 1620404 |
| D-K- |
| 15140-01-00 |
| 02/2016 |


Calibration result (3/3)
Kalibrierergebnis (3/3)

| Bin | Flow dir | Sensor out | Uncertainty | Flow speed |
|-----|----------|------------|-------------|------------|
| - | deg | deg | deg | m/s |
| 63 | 315.01 | 315.55 | 0.8 | 8.195 |
| 64 | 320.06 | 320.54 | 0.8 | 8.196 |
| 65 | 325.06 | 325.55 | 0.8 | 8.199 |
| 66 | 330.04 | 330.60 | 0.8 | 8.199 |
| 67 | 334.98 | 335.60 | 0.8 | 8.197 |
| 68 | 340.04 | 340.64 | 0.8 | 8.198 |
| 69 | 345.02 | 345.63 | 0.8 | 8.197 |
| 70 | 350.01 | 350.71 | 0.8 | 8.198 |
| 71 | 355.04 | 355.74 | 0.8 | 8.196 |

File: 1620404

| | | |
|-----------------------------------|--------|-----------------|
| Linear regression analysis | Slope | 0.99916 deg/deg |
| | Offset | 0.7734 deg |

Graphical representation of the result
Grafische Darstellung des Ergebnisses



| |
|-------------|
| 1620404 |
| D-K- |
| 15140-01-00 |
| 02/2016 |

Photo of the measurement setup
Foto des Messaufbaus



Remark: The proportions of the set-up may not be true to scale due to imaging geometry.