

ESMAPBD BDFE2
Data Report WINDCUBEv2 S/N WLS7-598
at the site Feni,
Chittagong District, Bangladesh
for the period from
2018-08-01 to 2018-08-31

2018-09-03


Summary report: SG17010KB19

ESMAPBD BDFE2

Data Report WINDCUBEv2 S/N WLS7-598

at the site Feni, Chittagong District, Bangladesh

Summary report: SG17010KB19

Location or measuring site:	E 91.358190, N 22.800290, Feni, Chittagong District / Bangladesh		
Client:	Suntrace GmbH	Große Elbstraße 145c D-22767 Hamburg	
	On behalf of Worldbank Group	1818 H Street, NW Washington, DC 20433	
Contractor:	windtest grevenbroich gmbh Frimmersdorfer Str. 73a D-41517 Grevenbroich		
Date of order:	2017-09-12	Contract number:	17 0091 09
Auditor:	Editor:		

Dipl.-Ing. Frank Albers
Division manager energy assessment

Dipl.-Ing. Florian Schmidt
Project manager site assessment

Grevenbroich, 2018-09-03

This summary may only be copied in extracts with the written consent of windtest grevenbroich gmbh.
It comprises 12 pages in total, incl. appendices.



CONTENTS

1	Introduction.....	4
2	Measurement statistics	4
3	Time series.....	5
4	Daily profile.....	6
5	Wind direction distribution	7
6	Natural turbulence	7
7	Wind profile.....	8
8	Station Log.....	9
9	Appendix	11
9.1	Processing	11



1 Introduction

windtest grevenbroich gmbh (wtg) was instructed by Suntrace GmbH to evaluate the data of the LiDAR wind measurement system at the location Feni. This report only contains the data measured by the LiDAR device ranging from 2018-08-01 until 2018-08-31 at the present site. In parallel an environmental measurement including a small meteorological mast (10 m) is being performed by the customer. The results of these measurements can be taken from a separate report provided by the customer.

2 Measurement statistics

Table 1: Mean measurement values during the evaluation period

Mean Values	Wind speed [m/s]	Wind speed max [m/s]	Wind speed min [m/s]	Wind direction [°]	Weibull A [m/s]	Weibull k []	Availability [%]
40 m	5,62	16,75	0,66	170,1	6,29	2,699	96,0
60 m	6,35	13,77	0,62	171,3	7,08	2,806	91,5
80 m	6,73	19,11	0,53	172,4	7,51	2,896	86,1
100 m	6,98	14,58	0,68	173,5	7,79	3,046	80,3
110 m	7,10	14,72	0,45	174,4	7,94	3,132	77,5
120 m	7,23	18,73	0,51	175,1	8,08	3,152	75,3
130 m	7,34	15,26	0,61	175,7	8,20	3,232	73,4
140 m	7,46	21,85	0,62	176,4	8,31	3,261	71,7
150 m	7,53	15,14	0,45	176,8	8,40	3,379	70,8
160 m	7,63	15,11	0,74	177,4	8,51	3,452	69,7
180 m	7,82	17,65	0,83	178,1	8,72	3,573	68,0
200 m	7,94	16,68	0,79	178,8	8,85	3,664	68,0

Table 2: Availability during the evaluation period

Availability per day [%]	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
40 m	96	92	100	100	100	75	98	100	100	100	97	100	93	85	97	92	96	93	92	100	99	100	92	94	96	99	100	99	98	97	99
60 m	95	89	100	100	99	52	92	100	100	100	92	94	85	72	88	77	82	92	90	99	97	100	88	92	81	96	100	98	97	92	96
80 m	93	78	100	100	89	37	85	100	97	100	83	83	82	65	75	63	65	92	92	99	97	100	83	88	62	92	100	98	97	88	87
100 m	91	65	100	99	72	26	85	100	91	100	69	77	76	50	52	51	44	91	94	99	97	100	85	85	42	88	100	98	96	86	77
110 m	91	61	100	99	66	20	85	100	89	100	58	72	76	41	44	42	34	90	94	99	97	100	85	85	39	88	100	98	95	83	75
120 m	91	54	100	99	61	21	84	100	83	100	51	69	74	35	39	35	27	88	93	99	96	100	85	85	34	85	100	98	95	83	71
130 m	91	55	100	99	57	16	82	100	81	100	45	69	74	20	33	30	24	87	92	99	96	100	84	83	34	83	100	98	95	82	69
140 m	91	53	100	99	57	11	82	100	78	100	36	67	73	15	32	24	19	87	92	99	95	100	83	83	29	82	100	98	94	78	67
150 m	91	53	100	99	51	8	83	100	78	100	35	65	72	8	31	24	16	87	90	99	95	100	82	83	29	81	100	98	94	76	67
160 m	89	51	100	99	51	4	82	100	76	100	34	64	72	6	31	19	13	86	90	99	96	100	83	81	26	81	100	98	94	72	66
180 m	88	52	100	99	49	1	82	100	70	100	26	65	67	1	30	16	9	87	83	99	96	100	81	77	24	80	100	98	90	71	65
200 m	88	52	100	99	49	1	82	100	70	100	26	65	67	1	30	16	9	87	83	99	96	100	81	77	24	80	100	98	90	71	65



3 Time series




Figure 1: Time series of wind speed during the evaluation period




Figure 2: Time series of wind direction during the evaluation period



4 Daily profile




Figure 3: Daily profile of wind speed during the evaluation period




Figure 4: Daily profile of wind direction during the evaluation period



5 Wind direction distribution




Figure 5: Frequency distribution of wind direction during the evaluation period

6 Natural turbulence




Figure 6: Directional mean turbulence during the evaluation period



7 Wind profile




Figure 7: Wind profile during the evaluation period



8 Station Log

Date	Note	Issues
2017-06-04	Installation of LiDAR (Florian Schmidt, wtg) Connection to utility grid due to charger problems with 24 V	frequent restarts
2017-06-15	Manufacturer recommends to turn off LiDAR due to frequent restarts	frequent restarts
2017-06-16	LiDAR disconnected from Grid (Najmul Hossain, EQMS)	LiDAR disconnected
2017-07-27	Installation of DC-AC converter to supply LiDAR (Najmul Hossain, EQMS) LiDAR connected to power supply Performance check via remote connection (Florian Schmidt, wtg)	-
2017-07-28	Performance check via remote connection (Florian Schmidt, wtg)	-
2017-07-31	Data and performance check (Florian Schmidt, wtg) No connection to LiDAR	According to sent data, most likely no present LiDAR issues
2017-08-08	Data connection restored Data and performance check (Florian Schmidt, wtg)	-
2017-09-05	No connection to LiDAR	According to sent data, most likely no present LiDAR issues
2017-09-09	Data connection restored Data and performance check (Florian Schmidt, wtg)	-
2017-12-04	No connection to LiDAR	According to sent data, most likely no present LiDAR issues
2017-12-05	Data connection restored Data and performance check (Florian Schmidt, wtg)	-
2018-01-02	No connection to LiDAR	According to sent data, most likely no present LiDAR issues
2018-01-03	Data connection restored Data and performance check (Florian Schmidt, wtg)	-
2018-01-30	No connection to LiDAR	According to sent data, most likely no present LiDAR issues
2018-02-06	Data connection restored Data and performance check (Florian Schmidt, wtg)	-
2018-05-01	LiDAR shut down (02:20 - 02:30) LiDAR shut down (04:30 - 06:10)	No power supply / Low solar radiation due to heavy rain
2018-05-04	LiDAR shut down (10:50 - 12:10)	No power supply / Low solar radiation due to heavy rain
2018-05-07	LiDAR shut down (02:10 - 03:20) LiDAR shut down (11:20 - 12:30)	No power supply / Low solar radiation due to heavy rain
2018-05-15	LiDAR shut down (10:30 - 12:40)	No power supply / Low solar radiation due to heavy rain
2018-06-05	LiDAR shut down (10:50 - 12:10)	No power supply / Low solar radiation due to heavy rain
2018-07-11	LiDAR shut down (10:10 - 13:20)	No power supply / Low solar radiation due to cloudy conditions
2018-07-13	LiDAR shut down (09:50 - 13:00)	No power supply / Low solar radiation due to cloudy conditions



Date	Note	Issues
2018-07-15	LiDAR shut down (10:40 - 13:20)	No power supply / Low solar radiation due to cloudy conditions
2018-08-02	LiDAR shut down (10:40 - 10:50)	No power supply / Low solar radiation due to cloudy conditions
2018-08-06	LiDAR shut down (12:50 - 14:10)	No power supply / Low solar radiation due to cloudy conditions

Note: Weekly and other frequently performed checks as well as data backup will not be listed in the station log.

We hereby affirm that the evaluation was performed in accordance with the latest state of the art, impartially and to the best of our knowledge and belief.

Grevenbroich. 2018-09-03

Dipl.-Ing. Florian Schmidt
Project Manager



9 Appendix

9.1 Processing

Version	Date	Content
SG17010B1	2017-04-25	Verification of the remote sensing device type Leosphere WINDCUBE v2 S/N WLS7-598 performed at the verification station Grevenbroich
SG17010B2	2017-06-22	Installation of the Remote Sensing Device Type Leosphere WINDCUBE v2 S/N WLS7-598 at the site Feni
SG17010KB1	2017-08-31	ESMAPBD BDFE2 Cumulative Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni
SG17010KB2	2017-09-11	ESMAPBD BDFE2 Cumulative Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni
SG17010KB3	2017-10-06	ESMAPBD BDFE2 Cumulative Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni
SG17010KB4	2017-11-08	ESMAPBD BDFE2 Cumulative Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni
SG17010KB5	2017-12-18	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2017-11-01 to 2017-11-30
SG17010KB6	2018-01-17	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2017-12-01 to 2017-12-31
SG17010KB7	2018-03-02	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-01-01 to 2018-01-31
SG17010KB8	2018-03-02	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-02-01 to 2018-02-30
SG17010KB9	2018-04-13	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2017-06-01 to 2017-06-30
SG17010KB10	2018-04-13	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2017-07-01 to 2017-07-31
SG17010KB11	2018-04-13	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-03-01 to 2018-03-31
SG17010KB12	2018-05-24	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2017-08-01 to 2017-08-31
SG17010KB13	2018-05-24	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2017-09-01 to 2017-09-30
SG17010KB14	2018-05-24	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2017-10-01 to 2017-09-31
SG17010KB15	2018-05-24	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-04-01 to 2018-04-30
SG17010KB16	2018-06-06	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-05-01 to 2018-05-31
SG17010KB17	2018-07-03	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-06-01 to 2018-06-30
SG17010KB18	2018-08-10	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-07-01 to 2018-07-31
SG17010KB19	2018-09-03	ESMAPBD BDFE2 Data Report WINDCUBEv2 S/N WLS7-598 at the site Feni for the period 2018-08-01 to 2018-08-31



<i>Copy to</i>	<i>Copy no.</i>
Customer	1
Project folder	2

Copy no.: